

FAX TRANSMISSION

MINK HILL TIMBER FRAME HOMES, INC

285 Davis Road
Bradford, New Hampshire 03221
(603) 938-6219
Fax: (603) 938-6219
517-4703 pager #

To: Bruss Construction
Attn: Chris Simpkins
Date: October 30, 2006

Fax # 938-2621
Pages 2 including this cover sheet.

From: Kyle M Whitehead

Subject: Timber Bracket Proposal

Chris:

Attached is Timber Bracket Proposal for your review and comment.


Let me know if you have any questions or if there is something that I left out.

Thanks,



Kyle Whitehead

MINK HILL TIMBER FRAME HOMES INC
285 DAVIS ROAD
BRADFORD, NH 03221
(603)938-6219 PHONE/FAX
WWW.MINKHILLTIMBERFRAMES.COM



Date: October 29, 2006

PROPOSAL

Page 1 of 1

To:
 Bruce Construction
 PO Box 456
 Bradford, NH 03221

Project:
 (6) South wall exterior heavy timber brackets
 Green Woodlands
 Dorchester, New Hampshire

Scope of Work

Mink Hill Timber Frame Homes (MHTF) shall perform all work associated with the fabrication and erection of the (6) exterior heavy timber brackets for the South wall timber frame per Paradigm Builders Timber Frame sketches dated 10/26/06 and the following specifications:

Scope of work to include:

Fabrication of the heavy timber brackets at MHTF's shop in Bradford
 Installation of the heavy timber brackets on the timber frame residence in Dorchester, NH
 MHTF is to power plane the rough sawn timbers and sand timbers ready for exterior oil finish by others
 MHTF is to provide hand riven pegs for the mortise and tenon joinery
 MHTF's shall plug countersunk holes in the existing timber frame with Oak

Bruce Construction is to provide all necessary timbers rough sawn to MHTF shop in Bradford
 Bruce Construction is to install all necessary 5 x 8 blocking and headers in the exterior curtain wall

Material and Specifications:

Rough Sawn timbers supplied by Green Woodlands and delivered to MHTF's shop in Bradford
 Bruce Construction is to provide all necessary hardware
 MHTF is to end seal all timbers after joinery has been performed.
 MHTF to sand and finish power plane all timbers

MHTF's shall provide oak material for plugging countersunk washers in the existing timber frame

We propose to execute the (6) timber brackets - complete in accordance with the above specifications for the sum of:

Four thousand three hundred dollars

\$4,300.00

Acceptance of Proposal - The above prices, specifications and conditions are satisfactory and are hereby accepted. Additional work to be performed will be determined and priced at a later date. You are authorized to do the work as specified.

Signature _____

Date _____

Signature Kyle M. Whitehead

Date 10/30/06

Mink Hill Timber Frame Homes, Inc